SAGAR FOREST DIVISION.

Notification dated 25th November 1927.

It is hereby notified for general information that the logs described below were found lying unclaimed in Bettadakurli District Jungle, Kuppagadde hobli, Sorab Taluk.

Any person having any claim to these logs may present a written statement of such claim to the District Forest Officer, Sagar Division within one month from the date of the publication of this notification and establish the same to the satisfaction of the above Officer, failing which, the ownership of the timber shall vest in Government under Section 42 of the Mysore Forest Regulation.

The logs are now lying in the custody of Neelakantappa Gowda, Patel of Bettadakurli village, Sorab Taluk :—

Range	Kind of logs	Length	Girth	Cubic feet	Remarks
Sorab ...	1. Teak Sqr. ...	6—10	6—10	20	Bears no marks.
	2. Teak Rd. ...	11—4	3—0	6	

S. VENKATAVARADIENGAR,
District Forest Officer.

ENGINEERING DEPARTMENT.

WATER-SUPPLY DIVISION, BANGALORE.

Abstract Notification dated 9th November 1927.

The attention of the public is invited to the detailed notification calling for sealed tenders for laying an independent 8" Cast Iron Main Pipe from Champion Reefs Reservoir to Oorgaum Mines Tank, published on pages 1008 and 1009, Part VI of the *Mysore Gazette* dated 24th November 1927.

The last date for the receipt of tenders is 2nd December 1927.

H. R. VENKATASUBBA RAO.
Executive Engineer.

KOLAR DIVISION.

Dated 29th—30th November 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 3 P.M., on 10th January 1928, for restoring Chunchudenahalli Tank, Reg. No. 169 of Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 350 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Chunchudenahalli Tank of Kolar Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The quotations should be noted in figures as well as in words.

Items of work	Per	Quantity	Rate	Cost	Total
			Rs.	Rs.	
Bund to R. L. 54·50.					
Earth work to bund with watering and tamping	C.yd.	9,293			
Earth work excavation for puddle wall and used for bund.	"	59			
Puddle wall for hallaportion	"	65			
Turfing	S.yd.	7,447			
Clearing jungle prickly piers, etc.	Grade	..			
Cutting grips and trenches on old bund	Each	29			
New stone work revetment	C.yd.	810			
Grade stones with figures cut and painted together with Index stones.	Each	30			
Reg. No. and Date stone	"	1			
Gauge stone	"	1			
B. M. stones with figures cut and painted	"	1			
Old stone work to be reset	C.yd.	616			
Total					
Right weir 100' long at 50·00.					
Earth work excavation	C.yd.	103			
Stone jelly in surki mortar	C.ft.	431			
Burnt brick in surki mortar	"	1,196			
Burnt stone slabs	S.ft.	462			
Surki plastering	S.qr.	12·99			
Rough stone work	C.yd.	65			
Resetting old stone revetment	"	59			
Total					
Left weir 85' long at 50·00.					
Earth work excavation	C.yd.	37			
Burnt brick in surki mortar	C.ft.	444			
Burnt stone slabs	S.ft.	114			
Surki plastering	Sqr.	7·18			
Resetting old stone work (apron)	C.yd.	24			
Total					
Sluice No. I sill level at 45·00.					
Cutting open the bund and refilling the same	C.yd.	80			
Burnt brick in surki mortar	C.ft.	630			
Burnt stone slabs	S.ft.	178			
Surki plastering	Sqr.	4·97			
Cutting crifices					
Providing plug and rod with locking arrangements	Each	1			
Rough stone pitching in the rear	C.yd.	3			
Sluice No II.					
As per details in sluice No. I					
Grand Total for both the sluices					
Total					
Contingencies at 5%					
Grand Total					

Notice dated 29—30th November 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 3 P.M., on 9th January 1928, for Restoring Doddakallahalli Hosakere Tank, Reg. No. 248 of Malur Taluk. An approximate estimate of quantities is

given below. These quantities are not guaranteed The work should be completed by the end of December 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.—

Description of work.	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Doddakallahalli Hosakere tank of Malur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The quotations should be noted in figures as well as in words.

Items of work	Per	Quantity	Rate	Cost	Total
BUND.					
Earth work to Bund	C.yd.	2,898			
Turfing to bund	S.yd.	2,816			
Resetting old stone wherever necessary ...	Lump sum				
New stone work	C.yd.	195			
Puddle wall	,,	28			
Fixing grade stone with numbering and painting etc., complete.	No.	11			
Index stones	,,	11			
B.M. Stones	,,	2			
Register No. stone	,,	1			
Gauge stone	,,	1			
Jungle clearing	Grades	6			
Total to Bund ...	...	...	...	...	...
SLUICE.					
Earth work cutting open bund for construction of Tunnel.	C.yd.	55			
Filling up the top	,,	64			
Surki concrete foundation	C.ft.	118			
Burnt brick in surki mortar	,,	463			
Burnt stone slabs 4" to 6" thick	S.ft.	193			
Surki plastering	Sqrs.	5·02			
Providing wooden plug and rod with locking arrangements.	Lump sum				
Drilling holes in slabs	Lump sum				
Total to Sluice ...	...	...	...	...	...

Items of work	Per	Quantity	Rate	Cost	Total
WEIR.					
Earth work excavation in gravelly soil ...	C.yd.	2,288			
Surkey concrete	C.ft.	180			
Burnt brick in surki mortar ...	,,	231			
Burnt stone slabs 6" thick...	S.ft.	267			
Plastering with surki mortar	S.qr.	4·34			
Stone work	C.yd.	121			
Fongue and grove joints in slabs	No.	6			
Total ...	...	...	...	...	...
Grand Total ...	...	...	...	...	...

Notice dated 28th—30th November 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 3 P.M., on 3rd January 1928, for maintenance work to Kandavara Tank, Chikballapur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for maintenance work to Kandavara Tank, Chikballapur Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Quotations should be furnished in figures as well as in words.

Items of work	Per	Rate	Quantity	Cost	Total
Earth work	C.yd.	...	9,081	...	...
Turfing	...	...	23,168	...	...
Total ...	...	...	...	...	...

Notice dated 28th—30th November 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 3 P.M. on 3rd January 1928, for maintenance work of Gopalakrishna Tank, Chikballapur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Maintenance work of Gopalakrishna Tank Chikballapur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The quantities should be noted in figures as well as in words.

Items of work	Per	Rate	Quantity	Cost	Total
Earth work	C.yd.	...	8,290		
Turfing	S.yd.	...	25,600		
Total ...	...	...	...	...	...

N. G. KRISHNA IYENGAR,
Executive Engineer.

MYSORE DIVISION.

Notice dated 24th November 1927.

The notice is hereby given that sealed tenders will be received for constructing bridges over the Rivers Cauvery and Kapila at T.-Narsipur, by the Executive Engineer, Mysore Division, up to 12 noon of 10th December 1927. An abstract of the estimate of quantities and conditions governing the tender, are published on pages 1006 and 1007, Part VI of the *Mysore Gazette* dated 24th November 1927.

V. V. KARVE,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated 17th November 1927.

The attention of the public is invited to the notice calling tenders for constructing Barr Huts at Shimoga *vide* pages 1004 and 1005 of the *Mysore Gazette*, Part VI, dated 24th November 1927.

M. A. SRINIVASACHARI,
Executive Engineer.